

### **FUNCTIONAL TEST**

**PFBFA-24-00-03-00/1** Issue F Pages

22

CASA		CASA	SPF, Aircraft System Engineering Department						
Aircraft			A330 MRTT						
Т	itle:		Green Aircraft and AC Network System	ircraft and AC Network System Functional Test					
S	umn	nary:							
1	II	NTRODUCTION .		3					
	1.1 1.2		AND ABBREVIATIONS						
2			CUMENTATION						
3	R	EQUIRED EQUIP	MENT	3					
4	D	EFINITIONS		3					
5	P	RELIMINARY INS	STRUCTIONS	4					
	5.1 5.2 5.3	SAFETY INSTRUCTION	NS	4					
6	Т	EST EXECUTION	l	5					
	6.1 6.2 6.3 6.4 6.5 6.6 6.7	GROUND SERVICE CO LOSS OF THE TR1, TI SWITCHING OF THE E LOSS OF THE ELECTR SWITCHING OF DC M	RAFT ELECTRICAL CIRCUITS FROM BATTERIES 1 & 2						
7	Т	EST RESULTS		16					
	7.1 7.2 7.3 7.4 7.5 7.6 7.7	GROUND SERVICE CO LOSS OF THE TR1, TI SWITCHING OF THE E LOSS OF THE ELECTR SWITCHING OF THE D	RAFT FROM BATTERIES 1 & 2 ONFIGURATION. R2 AND ESS TR SS BUS 9XP RICAL NETWORK WITH THE BUS TIE DC MAIN GENERATION OF THE EMERGENCY GENERATOR						
			f. This document shall be neither used nor com						
Prepared by:		•	Checked by:	Approved by:					
_	_	Paul Martín L	·	Germán Soriano Rull					
S	igna	ture:	Signature:	Signature:					
D	ate:	12-01-201	Date:	Date: 20_03_2012					

#### **REVISIONS RECORD**

Issue	Revision Reason	Approved
Date	Chapters, Sections, Affected pages	Signature
А	New Issue	Casildo Calderon
29/09/08	All pages	
В	New Issue	Casildo Calderon
15/01/09	All pages	
С	New distributions on performance	Casildo Calderon
14/12/09	All pages	
D	New distributions on performance	Casildo Calderon
26/05/10	All pages	
Е	Update steps 6.2.3 and 6.2.5 Step 6.2.1 and 6.2.2 swapped	Casildo Calderon
27/10/10	Page 7	
	Applicable documentation updated	G. Soriano
	Page 4 Page 6	

#### 1 INTRODUCTION

#### 1.1 Object

The purpose of this test is to check the integrity and functionality of the Aircraft Electrical Power System (ATA24) after the installation of the EEN for powering the new Military Systems. This test is performed with external power and therefore generator tests are excluded in this part.

#### 1.2 List of acronyms and abbreviations

AMM	Aircraft Maintenance Manual	
EIS	Electronic Instrument System	
ECAM	Electronic Centralized Aircraft Monitoring	

#### **2 APPLICABLE DOCUMENTATION**

24-00-00-861-801	Energize the Aircraft Electrical Circuits from the External Power A
24-41-00-862-801	De-energize the Aircraft Electrical Circuits from the External Power A
31-60-00-860-801	EIS start procedure (EWD DU, SD DU only)
45-10-00-860-808	Get the SYSTEM REPORT/TEST ELEC: DC page

### **3 REQUIRED EQUIPMENT**

N/A

#### 4 DEFINITIONS

N/A

#### 5 PRELIMINARY INSTRUCTIONS

#### 5.1 Test Preparation

The systems to be operative for the test performance are the EIS and ECAM for the electrical system monitoring.

#### 5.2 Safety Instructions

Prior to performing any test, the following requirements must be met:

- Adequate electrical fire, extinguishing equipment shall be available within the aircraft and shall be within calibration / maintenance.
- No other testing shall be executed simultaneously on the aircraft, which might interfere with the correct execution of these tests.
- All Operator Safety hazards shall be identified and appropriate clothing, and or precautions shall be taken.
- Check that all control switches, and selectors of the electrical installation are in the OFF position.

### 5.3 Preliminary Actions

- All the engines and the APU shall be shut down.
- Batteries will be checked for correct connectivity. They shall also be checked to ensure they are fully charged.
- The wiring continuity tests of the system-under-test shall have been concluded successfully.
- The equipment and components of the system-under-test shall have been properly installed, in accordance with the applicable documentation. They shall be verified as fully operative.

#### 6 TEST EXECUTION

procedure)

WARNING: BEFORE POWER IS SUPPLIED TO THE AIRCRAFT, MAKE CERTAIN THAT ELECTRICAL CIRCUITS

UPON WHICH WORK IS IN PROGRESS ARE ISOLATED.

**NOTE:** All results are to be recorded in the Result Table below.

#### 6.1 Energize the Aircraft Electrical Circuits from Batteries 1 & 2

- 6.1.1 Apply procedure 24-41-00-861-801 of AMM. Energize the Aircraft Electrical Circuits from the External Power A.
  6.1.2 If EIS system is not operative, apply procedure 31-60-00-860-801 of AMM (EIS start
- 6.1.3 On the ECAM control panel, push the EL/AC key (on the SD, the ELEC AC page comes into view).
- 6.1.4 On the ELEC control panel 235VU, make sure that the BAT1 and BAT2 pushbutton switches are pushed, and then release the EXT A P/BSW.
- 6.1.5 Check that the AVAIL legend of the EXT A pushbutton switches come on. PASS FAIL **COMMENT:** 6.1.6 On the EWD, hold the ELEC AC page and check that the STAT INV indications come into view (115V, 400Hz) FAIL PASS **COMMENT:** 6.1.7 On ELEC DC page, check that the BAT indications come into view **PASS FAIL COMMENT:** 6.1.8 On ELEC AC page, check that the green line between the static inverter and the AC ESS busbar indication comes into view. PASS FAIL **COMMENT:** 6.1.9 On ELEC AC page, check that the SHED indication comes into view near the AC ESS
- 6.1.10 On the SD, on the ELEC DC page, check that the SHED indication come into view near the DC ESS busbar indication.

PASS FAIL COMMENT:

FAIL

**COMMENT:** 

busbar.

PASS

6.1.11 Release the BAT1 and BAT2 pushbutton switches and check that the aircraft is deenergized.

#### 6.2 Ground Service Configuration

6.2.1 Make sure that CBs listed below are closed:

FIN	PANEL	LOCATION	DESIGNATION
4LE1	721VU	U05	CKPT LT CAPT+MISC
4LE2	722VU	R40	CKPT LT F/O+MISC

6.2.2 On the control panel 5001VE (Figure 1), set the GND SELEC CTL switch to ON.



Figure 1. Panel Location.

6.2.3	On the avionics	compartment,	check that	the	DOME	lights	operates	or	view	that	close
<b>RCCBs</b>	1XX, 2XX, 3XX a	nd 4XX					·				

PASS FAIL COMMENT:

- 6.2.4 On the panel 722VU, open the circuit breaker 6XG (M44).
- 6.2.5 On the avionics compartment, check that the DOME lights do not operates or view that open RCCBs 1XX, 2XX, 3XX and 4XX..

PASS FAIL COMMENT:

- 6.2.6 On the panel 722VU, close the circuit breaker 6XG (M44).
- 6.2.7 On the control panel 5001VE (Figure 1), set the GND SELEC CTL switch to OFF.

#### 6.3 Loss of the TR1, TR2 and ESS TR

6.3.1 On the ELEC control panel 235VU (*Overhead panel*), push the EXT A, BAT1 and BAT2 pushbutton switch. Check that the "AVAIL" legend of the EXT A pushbutton switch goes off and "ON" legend comes into view. Check in SD page EL/DC that TR1 supplies DC1 and DC BAT, and TR2 supplies DC2, and TR ESS supplies DC ESS (normal configuration).

PASS FAIL COMMENT:

6.3.2 On the panel 715VU, open the C.B. 3XN1 (coordinate H55).

6.3.3 On the EWD, on the ELEC DC page, check that the TR1 indication is lost and SD display is lost.
PASS FAIL COMMENT: 6.3.4 Check that the green line between the DC2, DC1 and DC BAT busbar indications comes
into view.  PASS FAIL COMMENT:
6.3.5 On the EWD, check that the TR1 FAULT warning is <b>not</b> shown.  PASS FAIL COMMENT:
6.3.6 On the panel 715VU, close the C.B. 3XN1 (coordinate H55).
6.3.7 On the SD, on the ELEC DC page, check that the TR1 indication come in to view.  PASS FAIL COMMENT:
6.3.8 Check that the green line between the TR1, DC1 and DC BAT busbar indications comes into view.
PASS FAIL COMMENT:
6.3.9 Check that the green line between the DC2 and DC BAT busbar indication is lost.  PASS FAIL COMMENT:
6.3.10 On the panel 715VU, open the C.B. 3XN2 (coordinate V56) and on panel 722VU, open C.B. 42XN (coordinate B46).
6.3.11 On the SD, on the ELEC DC page, check that the TR2 indication is lost.  PASS FAIL COMMENT:
6.3.12 Check that the green line between the DC1, DC2 and DC BAT busbar indications comes into view.
PASS FAIL COMMENT:
6.3.13 On the EWD, check that the TR2 FAULT warning is <b>not</b> shown.  PASS FAIL COMMENT:
6.3.14 On the panel 715VU, close the C.B. 3XN2 (V56) and on panel 722VU, close C.B. 42XN (B46).
6.3.15 On the SD, on the ELEC DC page, check that the TR2 indication come in to view.  PASS FAIL COMMENT:
6.3.16 Check that the green line between the TR2, DC2 busbar indications comes into view.  PASS FAIL COMMENT:
6.3.17 Check that the green line between the DC2 and DC BAT busbar indication is lost.  PASS FAIL COMMENT:
6.3.18 On the panel 721VU, open the C.B. 5XC (coordinate M14).
6.3.19 On the SD, on the ELEC DC page, check that TR ESS indication is lost.  PASS FAIL COMMENT:

6.3.20 Check that the AC ESS indication comes on amber.  PASS FAIL COMMENT:
6.3.21 Check that the SHED indication comes into view near the AC ESS busbar indication.  PASS FAIL COMMENT:
6.3.22 On the EWD, Check that the TR ESS FAULT warning is <b>not</b> shown.  PASS FAIL COMMENT:
6.3.23 On the ELEC control panel 235VU, the FAULT legend of the AC ESS FED warning is shown.  PASS FAIL COMMENT:
6.3.24 On the panel 721VU, close the C.B. 5XC (coordinate M14).
6.3.25 On the SD, on the ELEC DC page, the system goes back to the normal configuration; TR1, TR2 and TR ESS indications are into view.  PASS FAIL COMMENT:
6.4 Switching of the ESS BUS 9XP
6.4.1 On the panel 715VU, open the C.B. 1XC (coordinate E54).
6.4.2 On the ELEC control panel 235VU, check that the FAULT legend of the AC ESS FEED pushbutton switch comes on.  PASS FAIL COMMENT:
6.4.3 On the SD, on the ELEC AC page, check that the AC ESS indication comes on amber.  PASS FAIL COMMENT:
6.4.4 On the SD, on the ELEC AC page, check that the SHED indication comes into view near the AC ESS busbar indication.  PASS FAIL COMMENT:
<ul><li>6.4.5 On the EWD, check that the AC ESS BUS FAULT and AC ESS BUS SHED warnings come into view.</li><li>PASS FAIL COMMENT:</li></ul>
6.4.6 On the ELEC control panel 235VU, release the AC ESS FEED pushbutton switch.
6.4.7 Check that the FAULT legend of the AC ESS FEED pushbutton switch goes off and the ALTN legend comes on.  PASS FAIL COMMENT:
6.4.8 On the SD, on the ELEC AC page, the green line between the AC2 and the AC ESS busbar indication comes into view.  PASS FAIL COMMENT:

6.4.9 Check that the SHED indication goes out of view.  PASS FAIL COMMENT:
6.4.10 On the EWD, check that the AC ESS BUS FAULT and AC ESS BUS SHED warnings go out of view.  PASS FAIL COMMENT:
6.4.11 On the panel 715VU, open the C.B. 2XC (S57).
6.4.12 On the ELEC control panel 235VU, check that the FAULT legend of the AC ESS FEED pushbutton switch comes on and the ALTN legend stays on.  PASS FAIL COMMENT:
6.4.13 On the SD, on the ELEC AC page, the AC ESS indication stays amber.  PASS FAIL COMMENT:
6.4.14 Check that the SHED indication comes into view near the AC ESS busbar indication.  PASS FAIL COMMENT:
6.4.15 On the EWD, check that the AC ESS BUS FAULT and AC ESS BUS SHED warnings come into view.  PASS FAIL COMMENT:
6.4.16 On the panel 715VU, close the C.B. 2XC (S57).
6.4.17 On the ELEC control panel 235VU, the FAULT legend of the AC ESS FEED pushbutton switch goes off and the ALTN legend stays on.  PASS FAIL COMMENT:
<ul><li>6.4.18 On the SD, on the ELEC AC page, the green line between the AC2 and the AC ESS busbar indications comes into view.</li><li>PASS FAIL COMMENT:</li></ul>
6.4.19 Check that the SHED indication goes out of view.  PASS FAIL COMMENT:
6.4.20 On the EWD, the AC ESS BUS FAULT and AC ESS BUB SHED warnings go out of view.  PASS FAIL COMMENT:
6.4.21 On the panel 715VU, close the C.B. 1XC (coordinate E54) and on the ELEC control panel 235VU, push the AC ESS FEED pushbutton switch.
6.4.22 On the ELEC control panel 235VU, check that the ALTN legend of the AC ESS FEED pushbutton switch goes off.  PASS FAIL COMMENT:
6.4.23 On the SD, on the ELEC AC page, check that the green line between the AC2 and the AC ESS busbar indications goes out of view.  PASS FAIL COMMENT:

6.4.24 Check that the green line between the AC1 and the AC ESS busbar indication comes into
PASS FAIL COMMENT:
6.5 Loss of the Electrical Network with the BUS TIE Pushbutton switch
6.5.1 On the ELEC control panel 235VU, release the BUS TIE pushbutton switch.
<ul><li>6.5.2 On the ELEC control panel 235VU, the OFF legend of the BUS TIE pushbutton switch comes on.</li><li>PASS FAIL COMMENT:</li></ul>
<ul><li>6.5.3 On the SD, on the ELEC AC page, the green line between the AC1 and AC2 busbar indications goes out of view.</li><li>PASS FAIL COMMENT:</li></ul>
6.5.4 Push the BUS TIE pushbutton switch.
6.5.5 On the ELEC control panel 235VU, the OFF legend of the BUS TIE pushbutton switch goes off.  PASS FAIL COMMENT:
<ul> <li>6.5.6 On the SD, on the ELEC AC page, the green line between the AC1 and AC2 busbar indications comes into view.</li> <li>PASS FAIL COMMENT:</li> </ul>
6.6 Switching of DC Main Generation
6.6.1 Apply procedure 45-10-00-860-808 of AMM. On the MCDU, get the SYSTEM REPORT/TEST ELEC: DC page. Push the MCDU MENU mode key. Push the line key adjacent to the CMS indication. Push the line key adjacent to the SYSTEM REPORT/TEST indication.
6.6.2 On the panel 715VU, open C.B. 3PU1 (J55).
<ul><li>6.6.3 On the SD, on the ELEC DC page, check that the TR2 energizes the DC1, DC2 and DC BAT busbars.</li><li>PASS FAIL COMMENT:</li></ul>
6.6.4 On the EWD, check that the TR1 FAULT warning comes into view.  PASS FAIL COMMENT:
6.6.5 On the panel 715VU, close C.B. 3PU1 (J55).

6.6.6 On the MCDU, on the ELEC DC page, push the line key adjacent to the TR1 indication and then push the line key adjacent to the TR1 RESET indication.

6.6.7 On the EWD, check that the TR1 FAULT warnings goes out of view.  PASS FAIL COMMENT:
6.6.8 On the SD, on the ELEC DC page, check that the normal configuration comes into view.  PASS FAIL COMMENT:
6.6.9 On the panel 721VU, open C.B. 6XM (K05).
6.6.10 On the SD, on the ELEC DC page, check that DC1 busbar no longer supplies the DC BAT busbar.
PASS FAIL COMMENT:
6.6.11 Check that DC2 busbar supplies the DC BAT busbars.  PASS FAIL COMMENT:
6.6.12 On the SD, on the ELEC AC page, check that AC1 indication goes amber.  PASS FAIL COMMENT:
6.6.13 On the panel 721VU, close C.B. 6XM (K05).
6.6.14 On the SD, on the ELEC DC page, check that DC1 busbar supplies the DC BAT busbar.  PASS FAIL COMMENT:
6.6.15 Check that DC2 busbar no longer supplies the DC BAT busbars.  PASS FAIL COMMENT:
6.6.16 On the SD, on the ELEC AC page, check that TR1 indication back white.  PASS FAIL COMMENT:
6.6.17 On the panel 715VU, open the C.B. 3PU2 (W56).
6.6.18 On the SD, on the ELEC DC page, check that the TR1 energizes the DC1, DC2 and DC BAT busbars.  PASS FAIL COMMENT:
6.6.19 On the EWD, check that the TR2 FAULT warning comes into view.  PASS FAIL COMMENT:
6.6.20 On the panel 715VU, close the C.B. 3PU2 (W56).
6.6.21 On the MCDU, on the ELEC DC page, push the line key adjacent to the TR2 indication and then push the line key adjacent to the TR2 RESET indication.
6.6.22 On the EWD, check that the TR2 FAULT warnings goes out of view.  PASS FAIL COMMENT:
6.6.23 On the SD, on the ELEC DC page, check that the normal configuration comes into view.  PASS FAIL COMMENT:

6.6.24 On the AC/DC emergency power center 742VU, open the C.B. 4PE (R76).

6.6.25 On the SD, on the ELEC DC page, check that the DC ESS busbar is supplied by DC BAT.  PASS FAIL COMMENT:
6.6.26 On the EWD, check that the TR ESS FAULT warning comes into view.  PASS FAIL COMMENT:
6.6.27 On the AC/DC emergency power center 740VU, close the C.B. 4PE (R76).
6.6.28 On the panel 715VU, open C.B. 3PU1 (J55).
6.6.29 On the SD, on the ELEC DC page, check that the TR2 energizes the DC2, DC BAT and DC1 busbars.  PASS FAIL COMMENT:
6.6.30 On the EWD, check that the TR1 FAULT, DC ESS BUS and DC ESS BUS SHED warnings come into view. On ECAM, push CLR until warnings come into view  PASS FAIL COMMENT:




Figure 3. ECAM Control Panel.

6.6.31 On the panel 715VU, open the C.B. 3PU2 (W56).

	ELEC DC page, check that the ESS TR energizes the DC ESS busbar <b>COMMENT</b> :
	2 FAULT, DC BUS 2 and DC BUS 1 warnings comes into view.  COMMENT:

- 6.6.34 On the panel 715VU, close C.B. 3PU1 (J55).
- 6.6.35 On the MCDU, on the ELEC DC page, push the line key adjacent to the TR1 indication and then push the line key adjacent to the TR1 RESET indication. If MCDU is not operative, do a manual reset in TR 1. Press the RESET pushbutton switch of the TR1 and the red light goes off.




Figure 4. Transformer Rectifier.




Figure 5. Location TR1 (1PU1), TR2 (1PU2), TR3 (A7PU), TR4 (A3PU).

6.6.36	On the	EWD,	check that	the	TR1	FAULT,	DC	BUS	2,	DC	BAT	BUS	and	DC	BUS	1
	warnings	s goes	out of view.													

PASS FAIL COMMENT:

6.6.37 Check that the DC ESS BUS FAULT and DC ESS BUS SHED warnings come into view.

PASS FAIL COMMENT:

- 6.6.38 On the panel 715VU, close C.B. 3PU2 (W56).
- 6.6.39 On the MCDU, on the ELEC DC page, push the line key adjacent to the TR2 indication and then push the line key adjacent to the TR2 RESET indication.
- 6.6.40 On the EWD, check that the TR2 FAULT warning goes out of view.

PASS FAIL COMMENT:

6.6.41 On the MCDU, on the ELEC DC page, push the line key adjacent to the TR ESS indication and then push the line key adjacent to the TR ESS RESET indication.

6.6.42 On the EWD, check that the TR ESS FAULT warning goes out of view.  PASS FAIL COMMENT:
6.6.43 On the SD, check that the normal configuration comes into view.  PASS FAIL COMMENT:
6.7 Operational Test of the Emergency Generator Manual Connection on Batteries
6.7.1 On the ELEC control panel 235VU, release the BAT 1 pushbutton switch.
6.7.2 On the ELEC control panel 235VU, check that the OFF legend of the BAT 1 pushbutton switch comes on. PASS FAIL COMMENT:
6.7.3 On the control panel 211VU ( <i>Figure 6</i> ), lift the safety cover and Push and hold the EMER GEN TEST pushbutton switch.
21170
Figure 6. Cockpit Panel Location.
6.7.4 On the ELEC control panel 235VU, release the EXT A pushbutton switch.
6.7.5 On the ELEC control panel 235VU, check that the AVAIL legend of the EXT A pushbutton switch come on.  PASS FAIL COMMENT:
6.7.6 On the SD, get the ELEC AC page and make sure that stays in view.
6.7.7 On the SD, on he ELEC AC page, check that the green line between the AC1-1 and the AC  ESS busbar indications goes out of view.  PASS FAIL COMMENT:
6.7.8 Check that the AC ESS indication comes on green and the SHED indication comes into view near the AC ESS busbar indication. PASS FAIL COMMENT:
6.7.9 Check that the STAT INV indication comes on white.  PASS FAIL COMMENT:
6.7.10 Check that the STAT INV parameters (115V, 400Hz) come on green.  PASS FAIL COMMENT:

- 6.7.11 On the ELEC control panel 235VU, push the EXT A pushbutton switch.
- 6.7.12 On the control panel 211VU (Figure 6), release the EMER GEN TEST pushbutton switch.

6.7.13	$^{3}$ On the ELEC control panel 235VU, check that the AVAIL leg	end of the EXT A pushbutton
	switch goes off and the ON legend comes on.	

	, –	
PASS	FAIL	COMMENT:

6.7.14 Apply procedure 24-41-00-862-801 of AMM: De -energize the Aircraft Electrical Circuits from the External Power A if no more tests will take place.

#### **7 TEST RESULTS**

Type on the following tables the results of the tests:

## 7.1 Energize the Aircraft from Batteries 1 & 2.

STEP			SULT BOX)	-	COMMENT (IF FAIL)
6.1.5	AVAIL I	eger	nd of t	he I	EXT A pushbutton switches come on
0.1.5	PASS		FAIL		
6.1.6	STAT IN	۷V ir	ndicati	ons	come into view (115V, 400Hz)
0.1.0	PASS		FAIL		
6.1.7	BAT inc	dicati	ions co	ome	e into view
0.1.7	PASS		FAIL		
6.1.8	The gre	en li	ne bet	we	en the static inverter and the AC ESS busbar indication comes into view.
0.1.6	PASS		FAIL		
6.1.9	SHEDD	) indi	ication	CO	mes into view near the AC ESS busbar
0.1.9	PASS		FAIL		
6.1.10	SHEDD	) indi	ication	CO	mes into view near the DC ESS busbar
6.1.10	PASS		FAIL		
OVERAL			COM	EN	TS:
RESULT	(TICK				
BOX)		ı			
PASS					
FAIL					

## 7.2 Ground Service Configuration.

STEP			ESUL <sup>*</sup> BOX)		COMMENT (IF FAIL)
622	The DC	ME	lights	ope	rates
6.2.3	PASS		FAIL		
625	The DC	ME	lights	do n	ot operates
6.2.5	PASS		FAIL		
OVERAL	L TEST		COM	ENT	S:
RESULT (	TICK				
BOX)					
PASS					
FAIL					

## 7.3 Loss of the TR1, TR2 and ESS TR.

STEP			ESUL <sup>*</sup> BOX)	Γ	COMMENT (IF FAIL)
				and	DC BAT, and TR2 supplies DC2, and TR ESS supplies DC ESS
6.3.1	PASS		FAIL		
6.3.3	TR1 inc	licati	on is l	ost	
0.5.5	PASS		FAIL		
6.3.4		en li	ine be	twee	n the DC2, DC1 and DC BAT busbar indications comes into view
0.5.4	PASS		FAIL		
6.3.5				ng is	not shown
0.5.5	PASS		FAIL		
6.3.7				me ir	n to view
	PASS		FAIL		
6.3.8				twee	n the TR1, DC1 and DC BAT busbar indications comes into view
	PASS		FAIL	-	J. D.C. J. D.C. DATI. J.
6.3.9				twee	n the DC2 and DC BAT busbar indication is lost
	PASS		FAIL		
6.3.11	TR2 inc		FAIL	ost	
				h.v.o.c	n the DC1, DC2 and DC BAT busbar indications comes into view
6.3.12	PASS		FAIL	twee	IT THE DC1, DC2 and DC BA1 busbar indications comes into view
				nσ is	not shown
6.3.13	PASS		FAIL	11613	Tiot Shown
				me ir	n to view
6.3.15	PASS		FAIL		
	The gre	en li	ine be	twee	n the TR2, DC2 busbar indications comes into view
6.3.16	PASS		FAIL		
	The gre	en li	ine be	twee	n the DC2 and DC BAT busbar indication is lost
6.3.17	PASS		FAIL		
6 2 10	TR ESS	indi	cation	is lo	st
6.3.19	PASS		FAIL		
6.3.20	AC ESS	indi	ication	con	nes on amber
0.5.20	PASS		FAIL		
6.3.21	SHED i	ndic	ation o	ome	s into view near the AC ESS busbar indication
0.3.21	PASS		FAIL		
6.3.22				arnin	g is not shown
0.5.22	PASS		FAIL		
6.3.23				the A	AC ESS FED warning is not shown
0.5.25	PASS		FAIL		
6.3.25				oack	to the normal configuration
0.5.25	PASS		FAIL		

STEP			ESULT BOX)	COMMENT (IF FAIL)
OVERALL TEST RESULT (TICK BOX)			COMENT	·S:
PASS				
FAIL				

# 7.4 Switching of the ESS BUS 9XP

STEP	STEP RESU		COMMENT (IF FAIL)
612	FAULT legend	of the	AC ESS FEED pushbutton switch comes on
6.4.2	PASS FA	L	
6.4.3	AC ESS indicati	on cor	nes on amber
0.4.5	PASS FA	L	
6.4.4	SHED indication	com	es into view near the AC ESS busbar indication
0.4.4	PASS FA	L	
6.4.5	AC ESS BUS FA	ULT a	and AC ESS BUS SHED warnings come into view
0.4.5	PASS FA	L	
6.4.7	FAULT legend	of the	AC ESS FEED pushbutton switch goes off and the ALTN legend comes on
6.4.7	PASS FA	L	
6.4.8	The green line l	etwe	en the AC2 and the AC ESS busbar indication comes into view
0.4.8	PASS FA	L	
6.4.9	SHED indication	goes	out of view
6.4.9	PASS FA	L	
6.4.10	AC ESS BUS FA	ULT a	and AC ESS BUS SHED warnings go out of view
6.4.10	PASS FA	L	
6.4.12	FAULT legend	of the	AC ESS FEED pushbutton switch comes on and the ALTN legend stays on
0.4.12	PASS FA	L	
C 4 12	AC ESS indicati	on sta	ys amber
6.4.13	PASS FA	L	
C A 1 A	SHED indication	com	es into view near the AC ESS busbar indication
6.4.14	PASS FA	L	
C A 15	AC ESS BUS FA	ULT a	and AC ESS BUS SHED warnings come into view
6.4.15	PASS FA	L	
	FAULT legend	of the	AC ESS FEED pushbutton switch goes off and the ALTN legend stays on
6.4.17	PASS FA	L	
6.4.10	The green line l	etwe	en the AC2 and the AC ESS busbar indications comes into view
6.4.18	PASS FA	L	
	SHED indication	goes	out of view
6.4.19	PASS FA	L	

STEP			ESUL <sup>*</sup> BOX)	Γ	COMMENT (IF FAIL)
1 6 4 20	AC ESS <b>PASS</b>		FAIL	LT a	nd AC ESS BUB SHED warnings go out of view
6 4 22	ALT leg	gend	of the	AC	ESS FEED pushbutton switch goes off
6 1 23		en li		twee	n the AC2 and the AC ESS busbar indications goes out of view
	PASS The gre		FAIL ne be	twee	en the AC1 and the AC ESS busbar indication comes into view
	PASS		FAIL		
OVERALI RESULT ( BOX)	_		COM	ENT	S:
PASS FAIL					

### 7.5 Loss of the Electrical Network with the BUS TIE

STEP			ESULT BOX)	Γ	COMMENT (IF FAIL)
6.5.2	OFF leg	gend	of the	BUS	S TIE pushbutton switch comes on
	PASS The gre		FAIL ne be	twee	en the AC1 and AC2 busbar indications goes out of view
6.5.3	PASS		FAIL		5
6.5.5	The OF	Fleg	end o	f the	BUS TIE pushbutton switch goes off
0.5.5	PASS		FAIL		
6.5.6	The gre	en li	ne be	twee	n the AC1 and AC2 busbar indications comes into view
0.5.0	PASS		FAIL		
OVERALI RESULT ( BOX) PASS	_		COM	ENT	S:
FAIL					

## 7.6 Switching of the DC Main Generation

STEP	STEP RESULT (TICK BOX)	COMMENT (IF FAIL)				
663	TR2 energizes the DC1, DC2 and DC BAT busbars					
6.6.3	PASS FAIL					
6.6.4	TR1 FAULT warning comes into view					

STEP	STEP RESULT (TICK BOX)			Γ	COMMENT (IF FAIL)
	PASS		FAIL		
6.6.7				ngs	goes out of view
	PASS		FAIL		
6.6.8		-		tion	comes into view
	PASS		FAIL		
6.6.10				nger	supplies the DC BAT busbar
	PASS		FAIL		
6.6.11			- • •	lies t	he DC1 and DC BAT busbars
0.0.11	PASS		FAIL		
6.6.12	TR1 ind			es ar	nber
0.0.12	PASS		FAIL		
6.6.14			- • •	lies t	he DC BAT busbar
0.0.17	PASS		FAIL		
6.6.15				nger	supplies the DC1 and DC BAT busbars
0.0.15	PASS		FAIL		
6.6.16	TR1 ind			ck gr	een
0.0.10	PASS		FAIL		
6.6.18				DC	1, DC2 and DC BAT busbars
0.0.10	PASS		FAIL		
6.6.19		ULT	warni	ng c	omes into view
0.0.12	PASS		FAIL		
6.6.22				ngs	goes out of view
0.0.22	PASS		FAIL		
6.6.23	Normal	conf	igurat	tion	comes into view
0.0.25	PASS		FAIL		
6.6.25	DC ESS	bus	bar is	supp	blied by DC BAT
0.0.25	PASS		FAIL		
6.6.26		FAU	LT wa	ırnin	g comes into view
0.0.20	PASS		FAIL		
6.6.29		ergiz	es the	DC	2, DC BAT and DC1 busbars
0.0.29	PASS		FAIL		
6.6.30		ULT,	DC E	SS E	BUS and DC ESS BUS SHED warnings come into view
0.0.50	PASS		FAIL		
6.6.32				the	DC ESS and DC ESS SHED busbars
0.0.32	PASS		FAIL		
6.6.33		ULT,	DC B	SUS :	2, DC BAT BUS and DC BUS 1 warnings comes into view
0.0.33	PASS		FAIL		
6.6.36				SUS :	2, DC BAT BUS and DC BUS 1 warnings goes out of view
0.0.30	PASS		FAIL		
6.6.37	DC ESS	BUS	and	DC I	ESS BUS SHED warnings come into view

STEP			ESUL <sup>*</sup> BOX)		COMMENT (IF FAIL)
	PASS		FAIL		
6 6 40	TR2 FA	ULT	warni	ng g	oes out of view
	PASS		FAIL		
6642	TR ESS	FAL	JLT wa	arnin	g goes out of view
6.6.42	PASS		FAIL		
C C 42	Normal	con	figura	tion	comes into view
6.6.43	PASS		FAIL		
OVERALL TEST RESULT (TICK BOX) PASS FAIL		COM	ENT	S:	

## 7.7 Operational Test of the Emergency Generator

STEP	STEP RESULT (TICK BOX)				COMMENT (IF FAIL)				
6.7.2	OFF leg	gend	of the	BA <sup>-</sup>	T 1 pushbutton switch comes on				
0.7.2	PASS		FAIL						
6.7.5	AVAIL legend of the EXT A pushbutton switch come on								
6.7.5	PASS		FAIL						
6.7.7	the green line between the AC1-1 and the AC ESS busbar indications goes out of view								
6.7.7	PASS		FAIL						
	AC ESS indication comes on green and the SHED indication comes into view near the AC ESS								
0		busbar indication							
	PASS		FAIL						
6.7.9	STAT II	STAT INV indication comes on white							
0.7.9	PASS		FAIL						
6710	STAT II	AT INV parameters (115V, 400Hz) come on green							
6.7.10	PASS		FAIL						
6742	AVAIL	AIL legend of the EXT A pushbutton switch goes off and the ON legend comes on							
6.7.13	PASS		FAIL						
OVERALL TEST RESULT (TICK BOX)			COM	ENT	S:				
PASS									
FAIL									

NOTE: In Case of NCS, write down its number on Table 1

N.C.S. Number	Date

Table 1

**NOTE:** After this functional test execution, stamp the correspondent operation on the Production Order.

**NOTE:** Every result sheet must be stamped and attached to Production Order.

STAMP:	
DATE:	